



कावासोती नगरपालिका नगर कार्यपालिकाको कार्यालय

गण्डकी प्रदेश, नेपाल

२०७३



प. सं. २०८३/८४

च. नं.

मिति २०८३/०६/२१

विषय : दरभाउँ भरी पेस गर्ने सम्बन्धमा ।

यस कावासोती नगरपालिकाको आ.व. २०८३/८४ मा कारितास नेपाल र कावासोती नगरपालिका बिच लागत साझेदारी योजना अन्तर्गत खरकट्टा विपद रोकथाम कावासोती नगरपालिका वडा नं. १२ र १३ कार्यको लागि बजेट विनियोजन भएकोमा सो निर्माण कार्यको लागि फर्म छनौट गर्नुपर्ने भएको हुँदा यस पत्र संग संलग्न रहेको BOQ रितपूर्वक भरी अजको मितिले ३ दिन कार्यलय समय भित्र पेश गर्नुहुन अनुरोध छ । साथै संलग्न रहेको BOQ रितपूर्वक भरी पेश गर्दा तपसिल बमोजिमको कागजात अनिवार्य संलग्न गर्नुहुन पत्राचार गरिन्छ ।

तपसिल

१. Firm or Company registration Certificate and Renew
२. VAT and PAN registration Certificate
३. Business Registration Licence and Renew
४. Tax Clearance Certificate / Tax return submission evidence / evidence of time extension latest fiscal year
५. यस नगरपालिकामा सूचीकृत गरेको प्रमाणपत्रको प्रतिलिपि ।

महेश पाण्डे

प्रमुख प्रशासकीय अधिकृत



Kawasoti Municipality
Office of The Municipal Executive
Kawasoti, Nawalparasi (East of Bardaghat Susta)
Gandaki Province, Nepal

BOQ

FY: 2082/083



Project Name : खरकट्टा विपद रोकथाम, कावासोती नगरपालिका वडा नं. १२ र १३

Location: वडा नं. १२ र १३

0

S.N.	Description of Works	Units	Quantity	Rate	Total Amount	Remarks
A. PROVISIONAL SUM						
1	Lab Testing and Submission of report	PS	1.00	10000.00	10000.00	
2	Information board(Notice board, Cautionary Board)	PS	1.00	5000.00	5000.00	
				Total of PS	15000.00	
B. CIVIL WORKS						
1	Roadway Excavation in all types of soil (MECHANICAL Means) as per drawing and technical specification, including shoring and bracing, removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer .	Cum	45.42			
2	Providing and laying of hand pack STONE SOLING and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	7.11			
3	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation with FORMWORK complete as per Drawing and Technical Specifications.	Cum	6.70			
4	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications (using mixer).	Cum	69.54			
5	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per Drawing and Technical Specifications. (Locally available Material, with out watering and compaction by tamping rod)	Cum	12.30			
			Total of civil work=			
			VAT 13%			
			Total Project Cos with Vat PS			

Name of Form

Sign

Stamp

011

[Signature]

[Signature]
महेन्द्र पाण्डे
प्रमुख प्रशासकीय अधिकृत